



सैन्ट्रल रेलसाइड वेअरहाउस कम्पनी लिमिटेड

(भारत सरकार का उद्यम)

आईएसओ 9001:2008 प्रमाणित कम्पनी

CENTRAL RAILSIDE WAREHOUSE COMPANY LIMITED

(A Govt. of India Enterprise)

An ISO 9001:2008 Certified Company

रोजा रोड - गुडगाव - गुडगाव - 110001, नई दिल्ली
CIN: U63023DL2007PLC165676



मिनी रत्न
Mini Ratna PSU



No. CRWC/V-RWC, Roza/16-17/9364

Date: 21.11.2016

NOTICE INVITING QUOTATION

Sealed percentage rate quotations are invited from the reputed contractors having valid electrical license for **Repair of electrical work in godown at RWC, Roza** as per schedule of work, terms and conditions enclosed.

Estimated cost of the work is **Rs. 3,01,261.00** (Rupees: Three lakh one thousand two hundred sixty one only). The quotation alongwith terms & conditions and schedule of work can be downloaded from websites www.cewacor.nic.in, www.tenderhome.com, and www.crowc.in up to **06.12.2016 upto 4:00 p.m.**

ELIGIBILITY CRITERIA

Contractors who fulfil the following requirements shall be eligible to apply. Joint ventures are not accepted.

(a) Contractor should have satisfactorily completed similar work i.e. electrical works during the last seven years ending last day of the month i.e. upto 30.11.2016 and completion certificate submitted as per the following requirements while submitting the quotation.

- | | |
|--|----------------|
| (i) One similar work costing not less than | Rs. 2.41 lakhs |
| or | |
| (ii) Two similar works each costing not less than | Rs. 1.81 lakhs |
| or | |
| (iii) Three similar works each costing not less than | Rs. 1.21 lakhs |

पंजीकृत एवं कॉर्पोरेट कार्यालय - भूतल, प्रगति मैदान मेट्रो स्टेशन बिल्डिंग, नई दिल्ली-110001, दूरभाष : 011-23379418, फैक्स : 011-23379434
Regd. & Corp. Office : Ground Floor, Pragati Maidan Metro Station Building, New Delhi-110001, Ph. 011-23379418, Fax : 011-23379434

Website : www.crowc.in

The value of executed work shall be brought to current costing level by enhancing value of work at simple rate of 7% per annum, calculated from the date of completion to the last date of receipt of tender.


The quotation documents alongwith terms & conditions and schedule of work can be downloaded from websites www.cewacor.nic.in, www.tenderhome.com. and www.crwc.in upto 16:00 hours on 06.12.2016.

The duly filled in Quotations in sealed cover alongwith self attested copies of experience certificate (s) valid electrical license, Service Tax Registration , PAN Card and EMD of Rs. 6025 /- in the form of DD/Cash/Pay Order in favour of Central Railside Warehouse Company Ltd., New Delhi superscribing the name of work alongwith terms & conditions duly signed by the contractor should reach the **DGM (Engineering) , CRWC Ltd., New Delhi** on or before **07.12.2016 upto 15:00** hours and the same will be opened at 15:30 hours on the same day in the presence of contractors who may wish to be present at below mentioned address.

Medium & Small Enterprises are encouraged to apply against the NIQ. Procurement Policy for Micro Small and Medium Enterprises (MSME's), October 2012, will be adopted, wherever applicable and in accordance with government guidelines related to NIQs.

Bidders submitting the quotation under MSME category shall produce the certificate of registration under MSME category.

MSME's having valid registration certificate are exempted from payment of NIQ cost and earnest money deposit.


DGM (Engineering) 18/11/16

Copy to:

1. DGM (F&A), CRWC, C.O., New Delhi.
2. Terminal Manager, RWC, Agra, U.P.
3. Notice Board,
4. Working contractors.



सैन्ट्रल रेलसाइड वेअरहाउस कम्पनी लिमिटेड

(भारत सरकार का उद्यम)

आईएसओ 9001:2008 प्रमाणित कम्पनी

CENTRAL RAILSIDE WAREHOUSE COMPANY LIMITED

(A Govt. of India Enterprise)


An ISO 9001:2008 Certified Company

सीआईएन यू63023डीएल2007पीएलसी165676

CIN:U63023DL2007PLC165676



मिनी रत्न
Mini Ratna PSU



SCHEDULE OF WORK

Name of work: Repair of electrical work in godown at RWC, Roza.

S. No.	Description	Qty.	Unit	Rate	Amount
1	Supply & laying for following size of aluminum armored Cable, insulated PVC sheathed/XLPE of 1.1KV grade, laying on cable tray. Make Polycabe , Havells, Universal & KEI. as required. (Note :-This items also includes labour cost of removing of faulty cable and jointing with new cable after checking , testing and charging etc.)				
	(a) 3.5 X 50 sq mm aluminum armored cable.	200.00	mtr.	408.00	81600
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
	a) 2x1.5 sq. mm + 1x1.5sq mm earth wire.	300.00	mtr.	77.00	23100
	b) 2x2.5sq mm + 1x2.5 sq. mm earth wire.	150.00	mtr.	110.00	16500
	c) 2x4sq mm + 1x4 sq. mm earth wire.	150.00	mtr.	150.00	22500
3.	Supplying and fixing 5 amps to 32 amps rating, 240/volts, "B" series, miniature circuit breaker suitable for lighting and other loads of following poles in the existing MCB DB complete with connections, testing & commissioning etc. as required.				
	a) Single pole MCB	50 nos.	each	86	4300
	b) Double pole MCB	30 nos.	each	171	5130
4	Supplying and fixing single pole blanking plate in the existing MCB DB complete etc. as required.	20 nos.	each	2	40
5	Repairing of 3 phase DB of Godown including servicing of the DB and replacement defective spares and connection etc. as required.	10 nos.	each	1324.00	13240
6	Repairing of single phase DB of Godown including servicing of the DB and replacement defective spares and connection etc. as required.	15nos.	each	670.00	10050
7	Repairing of existing light points including testing/checking and replacement faulty accessories and cleaning of luminaries etc., for	190 nos.	each	121.00	

	brining in working condition as required.				22990
8	Supply and installation 35 watt spiral CFL, fitting in Twister type holder including testing and commissioning of the circuit as per required. (location Godown NO.02 to 12) make Havells, phillips, CGL etc.	150 nos.	each	483.00	72450
9	Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box/ wooden block including connection etc as required.	150 nos.	each	19.00	2850
10	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
	a) 5/6 amps switch	80 nos.	each	17.00	1360
	b) 15/16 amp switch	30 nos.	each	38.00	1140
	c) 3 pin 5/6 amp socket outlet	10 nos.	each	21.00	210
	d) 6 pin 15/16 amp socket outlet	10 nos.	each	43.00	430
11	Supplying and fixing of 20 mm sizes of medium class flexible PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.	125.00	mtr.	27.60	3450
12	Supplying and fixing 63 amp. rating, four pole, 440 volts, MCB in the existing MCB DB complete with connections, testing and commissioning etc. as required.	5 nos.	each	1539.00	7695
13	Supplying and fixing 100 amp. rating, four pole, 440 volts, MCCB, Ics = 100% of Icu in the existing man Panel complete with connections, testing and commissioning etc. as required.	2 nos.	each	6113.00	12226
		TOTAL			Rs. 301261.00
(Rupees: Three lakh one thousand two hundred sixty one only).					

Contractor


DGM (Engineering)

Estimated cost as per item No. 01 to 13 **Rs. 301261.00** (Rupees: Three lakh one thousand two hundred sixty one only).

I/We hereby quote our rates as _____ %
(_____ Percent)

above the rates entered in the schedule of work

I/We hereby quote our rates as _____ %
(_____ Percent)

below the rates entered in the schedule of work

Contractor Signature with seal



TERMS AND CONDITIONS


1. Security Deposit will be deducted @10% of gross amount of each and every bill of the contractor which will be refunded after successful completion of defect liability period of 6 months. EMD deposited alongwith the quotation shall be adjusted against the security deposit.
2. Necessary taxes i.e., income tax, sale tax cess vat etc.(Except Service tax) will be deducted from the bill as per prevalent rate as on date.
3. Contractor will have to arrange all labour, T&P etc. required for the execution/completion of the work, at all vertical levels as per site condition. Safety of working labour's lies on contractor only.
4. Quantities given in the schedule may vary as per actual execution at site.
5. Work will have to be completed within two months from the date of issue of work order.
6. Work shall be executed strictly as per CPWD specification/Schedule.
7. CRWC reserves the right to accept or reject any or all the quotations without assigning any reason thereof.
8. The offer shall be valid for two months from the date of opening of quotation.
9. The rate should be excluding Service Tax or any other tax levied by the Central Government in lieu of service tax and the same will be reimbursed by CRWC over and above the schedule of rates, subject to the contractor submitting his bills/ invoices thereof.
10. If, the contractor, to whom work is awarded, fails to complete the work within stipulated period of two months then, Engineer in charge shall have discretion to impose to levy of compensation for delay to recover liquidated damages, if any, to the Company.
11. No advance payment shall be made at any time and payment shall be made only after execution of items/ work.
12. If, the work is not started by the contractor within 1/8th of stipulated time.

Or

The contractor having been given a notice in writing to rectify, reconstruct or replace any defective work or fails to complete the work within the stipulated date or persistently neglects to carry out his obligations under the contract and does not remedy it or take effective steps within 7 days after the notice, the Engineering -in- Charge shall have power to rescind the contract and the EMD, security deposit already deducted under the contract shall be liable to the forfeited.

13. The party will sign each paper of Quotations in token of acceptance of their offer.
14. In the event of any documents found forged/ fabricated/ tampered/ altered or manipulated, then the EMD of the Contractor would be forfeited and he would be debarred for participating in CRWC for 5 years.
15. Before quoting the rates, contractor in his own interest may visit the site under intimation to the Terminal Manager.
16. The contractor will have to abide by the labour laws and have to extend the statutory due benefit to the person deployed and the CRWC will not be held responsible for any compensation in case of any mis-happening during contract period.


Contractor


DGM (Engineering)